BRUHATH BENGALURU MAHANAGARA PALIKE

Yelahanka Division, Yelahanka Zone

Executive Engineeer
Yelahanka Division
B.B.M.P. Bengaluru - 64

No.EE/YNK-D/E-PMT/09/2018-19 Dated: 27-2-2019

APPROVED TENDER SCHEDULE –'B'

Item-60

Name of Work:-Providing childrens playing equipments at Amba Bhavani park in ward no 03 Attur

Sl	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri Sri NAVEEN KRISHNAIAH	
				Rate	Rate in Words
1	KSRRB 300-1. Earthwork excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications. MORTH / Chapter 3 Page No. 143 / Item No. 19.1, PWD SR 2018-19	Cum	9.00	211.00	Rupees Two Hundred Eleven Only
2	Providing and fixing pre cast solid cement concrete kerb stones made out of CC 1:2:4 with top and bottom width 114 and 165 mm respectively, 400mm high and 450mm in length finished with CM 1:3 plastering and finishing cutting including formwork, curing, including cost of materials, labour charges of machinery, loading and unloading, lead and lift, transportation ete.,complete Page No. 27 / Item No. 5.30 PWD SR 2018-19	Nos	93.00	380.00	Rupees Three Hundred Eighty Only
3	KSRB 2.8 : Providing and Filling in foundation with granite / trap broken metal 100mm. and down size, with approved sand including hand packing, ramming, watering, including cost of all materials and labour with all lead and lift. complete as per specifications. specification. No. KBS Page No. 7 / Item No. 2.15 of PWD SR 2018-19	Cum	54.00	2245.00	Rupees Two Thousand Two Hundred Forty Five Only
4	KSRB 15-19.1 : Providing and applying ready mix priming coat over concrete / masonry / asbestos cement sheet / plastered surfaces including preparing the surface after thoroughly cleaning of oil, grease, dirt and other foreign matter, and sand papering including cost of materials, labour, complete as per specifications. Page No. 124 / Item No. Item No. 15.80, PWD SR 2018-19	Sqm	14.70	35.00	Rupees Thirty Five Only

	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri Sri NAVEEN KRISHNAIAH	
				Rate	Rate in Words
5	KSRB 15-19.2 : Providing and applying spray painting in two coats (excluding priming coat) over concrete / masonry / asbestos cement sheet / plastered surfaces with flat wall paint of approved brand to give even shade after cleaning the surface of all dirt, dust and other foreign matter, and sand papering including cost of materials, labour, complete as per specifications.Page No. 124 / Item No. Item No. 15.81, PWD SR 2018-19	Sqm	14.70	82.00	Rupees Eighty Two Only
6	Providing Children play standard Sea Saw Seater Equipment : This equipment is made up of main beam 50mm MS pipe 'A' class of length 98mtr with two handles welded at the ends as a hand are made of 20mm 'A' class pipe. The main beam is pivoted to the bottom supports of 40mm MS pipes by bush bearing clamped by pivot joints which swivel over 28mm dia steel shaft which gets installed in the ground by meas of concrete 2 Nos. seats are made of 250 mm x 200 mm x 18 SWG MS sheets with T hand rest at the front. Air pipe are if ISI grade. All the pipes are painted with two coats of super set paint over a coat of protective Zinc chromate yellow oxide including fixing the play equipments in CC 1:2:4, curing etc., complete with all lead, lift, loading, unloading and any other incidental charges and as perthe draing and specification and direction of the engineer in charge of the work.	Each	1.00	25200.00	Rupees Twenty Five Thousand Two Hundred Only
7	Providing Children play Merry-go-Round equipment : Made of MS 'A' Class pipes. Main pillars in 100 mm dia fitted with shaft and two bearing the other cross members are in 25 & 20 mm MS A Class pipe the bottom ring is made out of 25mm of ring size is 1.20 mts dia fitted with four seats are in mental sats if 250 x 200 x 18 SWG handles are made out of 20mm NB pipes and othe supports are in 25mm MS 'A' Class pipes. All the pipes are painted with two coats of super set paint over a coat of protective Zinc chromate yellow oxide including fixing the play equipments in CC 1:2:4, curing etc., complete with all lead, lift, loading, unloading and any other incidental charges and as perthe draing and specification and direction of the engineer in charge of the work.	Each	2.00	25200.0	Rupees Twenty Five Thousand Two Hundred Only

	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri Sri NAVEEN KRISHNAIAH	
				Rate	Rate in Words
8	Providing Children Play 2 - Seater Swing : This Swing consosts of 2 Nos, seat of solid fibbed FP of size 480 mm x 180 mm x 3.5 mm supported by MS chains. The chains are supported by circular housing with bearing from which the chain in suspended. The main beam is of 50 mm MS 'A' class pipe Size of MS chain 30 mm x 20 mm x 5mm thick The 2 Nos inverted 'V' beams are of 50 mm 'A' class pipes secured at the top the main beam by means of CI castings (Heavy duty for elders) All pipes are of ISI grade all the pipes are painted with two coats of super set paitng over a coat of protective Zinc chromate yellow oxide including fixing the play equipments in CC 1:2:4, curing etc., complete with all lead, lift, loading, unloading and any other incidental charges and as perthe draing and specification and direction of the engineer in charge of the work.	Each	1.00	41400.00	Rupees Forty One Thousand Four Hundred Only
9	Providing Children Play Standard Swing : This Swing consosts of 2 Nos, seat of solid fibbed FP of size 480 mm x 180 mm x 3.5 mm supported by MS chains. The chains are supported by circular housing with bearing from which the chain in suspended. The main beam is of 50 mm MS 'A' class pipe Size of MS chain 30 mm x 20 mm x 5mm thick The 2 Nos inverted 'V' beams are of 50 mm 'A' class pipes secured at the top the main beam by means of CI castings (Heavy duty for elders) All pipes are of ISI grade all the pipes are painted with two coats of super set paitng over a coat of protective Zinc chromate yellow oxide including fixing the play equipments in CC 1:2:4, curing etc., complete with all lead, lift, loading, unloading and any other incidental charges and as perthe draing and specification and direction of the engineer in charge of the work.	Each	2.00	51000.00	Rupees Fifty One Thousand Only
10	Duck wheel	Each	2.00	61200.00	Rupees Sixty One Thousand Two Hundred Only
11	Mini Wheel	Each	2.00	20700.00	Rupees Twenty Thousand Seven Hundred Only
12	Duck Swing (2 seater)	Each	2.00	51400.00	Rupees Fifty One Thousand Four Hundred Only
13	FRP Mini Slide	Each	2.00	20700.00	Rupees Twenty Thousand Seven Hundred Only
14	Mini Slide	Each	1.00	14400.00	Rupees Fourteen Thousand Four Hundred Only
15	Jack Frame	Each	1.00	12600.00	Rupees Twelve Thousand Six

	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri Sri NAVEEN KRISHNAIAH	
				Rate	Rate in Words
16	Nest	Each	1.00	21600.00	Rupees Twenty One Thousand Six Hundred Only
17	Bear	Each	1.00	17100.00	Rupees Seventeen Thousand One Hundred Only
18	Spring Duck	Each	1.00	32400.00	Rupees Thirty Two Thousand Four Hundred Only

Signature of the Contractor

Executive Engineer,
Yelahanka Division,
BBMP, Bengaluru-64.